

ENGINEERING DEPARTMENT.

BANGALORE DIVISION.

Notice dated 6th June 1928.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M., on 25th June 1928, for restoring Horamavoo Tank, Regs. No. 159 of Bangalore Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form annexed showing the rates at which the different items specified will be executed.

3. (a) Percentages less than or above the estimated rates will not be accepted.

4. Each tender must be accompanied by a deposit of rupees one hundred and fifty only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Restoring Horamavoo Tank, Reg. No. 159 of Bangalore Taluk", in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond: in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract of quantities for Horamavoo Tank.

No.	Item of work	Quantity	Per unit	Rate
	<i>Bund.</i>			Rs. a. p.
1	Cutting grip and clearing jungle ...	20	Grade	
2	Earthwork to bund including watering and tamping...	5,700	C.yd.	
3	New stone revetment ...	596	"	
4	Old stone revetment, removing and resetting ...	100	"	
5	Turfing ...	5,064	S.yd.	
6	Providing and fixing new grade stone complete ...	19	Each	
7	Do Index stones ...	19	"	
8	Do B. M. stones ...	2	"	
9	Do Regd. No. stone ...	1	"	
10	Do Gauge stone ...	1	"	
	<i>Constructing 9" stoneware pipe sluice.</i>			
1	Earthwork cut open the bund and refilling with watering and tamping.	50	C.yd.	
2	Earthwork, excavation for foundation ...	32		
3	Surki concrete for filling in foundation ...	87	C.ft.	
4	Burnt brick in surki ...	162	"	
5	Burnt stone slabs 6" roughly dressed ...	50	S.ft.	
6	Surki mortar plastering ...	2.24	Sqr.	
7	Rough stone work new ...	19	C.yd.	
8	Stoneware pipes 3" including carting, laying, etc. ...	25	R.ft.	
9	Providing and fixing wooden plug and iron rods, etc. ...	1	No.	
	<i>Constructing waste weir.</i>			
1	Earthwork excavation for foundation ...	53	C.yd.	
2	Surki mortar concrete ...	225	C.ft.	
3	Burnt brick in surki mortar ...	276	"	
4	Burnt stone slabs roughly dressed and fixed ...	323	S.ft.	
5	Surki mortar plastering ...	3.00	S.qr.	
6	New stone apron with jelly packing ...	40	C.yd.	
7	Draft clearing ...	56	"	

R. W. SCALDWELL,
Executive Engineer.